Abstract estimate for constructing drains in Chikmagalur Town during 1938-39 and 1939-40.

No.	Items of work	Unit	Rate	Quantity	Cost
	I. Street drains.				
1	Constructing sylk pattern 3″ drains, including providing and fixing new 3″ thick check slabs dressed, on 4½″ surki concrete bed with 1:6 cement combination mortar and cement plastering ½″ (1:3) proportion complete	R.ft.	..	4,164	
2	Constructing sylk pattern drains 3″ with old burnt stone slabs including cutting longitudinally, dressing, removing and resetting, conveying and fixing on 4½″ surki concrete bed (1:6) cement combination mortar and cement plastering ½″ thick (1:3) proportion complete.	R.ft.	..	4,347	
3	Constructing road crossing with size stone in lime mortar abutments and 6″ thick burnt stone slabs covering complete	No.	..	11	
4	Raising the sides of drain wherever necessary; size stone in mortar	C.ft.	..	..	
5	Dismantling and resetting the steps of houses ..	S.ft.	..	..	
6	Putting extra stone jelly concrete in surki mortar for the bed of drains wherever the soil is soft ..	C.ft.	..	..	
	II. Collecting and Main Drains.				
1	Constructing silk pattern drains with 3″ thick burnt stone new check slabs dressed and fixed on 4½″ surki concrete bed (1:6) cement combination mortar including cement plastering ½″ thick (1:3) proportion complete:—				
	(*a*) 7″ (2) section	R.ft.	..	750	
	(*b*) 6″ (3) section	,,	..	515	
	(*c*) 5″ (2) section	,,	..	1,605	
	(*d*) 4″ (2) section	,,	..	1,645	
	(*e*) 4″ (1) section	,,	..	500	
2	Constructing road crossings with size stone in lime mortar abutments and 6″ new burnt stone slabs covering, etc., complete	No.	..	11	
3	Constructing storm water overflows	No.	..	3	
4	Raising the side of drains with stone in lime mortar wherever necessary	C.ft.	..	..	
5	Putting extra stone jelly concrete in surki mortar wherever soil is soft	C.ft.	..	..	
6	Dismantling and resetting steps of houses ..	S.ft.	..	..	
7	Earthwork cutting roads and forming and refilling where needed	C.yd.	..	..	

C. R. IYENGAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE INSPECTOR-GENERAL OF POLICE IN MYSORE, BANGALORE.

Notice No. T. C. 295—37-38, dated 19th November 1937.

The public are hereby informed that an Avery's Weigh-bridge to weigh motor vehicles is erected in the Office of the Inspector-General of Police in Mysore, Cenotaph Road, Bangalore City, and that motor vehicles brought for weighment will be weighed on payment of a fee of Rs. 10 for each weighment. A certificate of weighment will invariably be issued with each weighment so made.

F. A. HAMILTON,
Inspector-General of Police.